WA-ENV-NOI-012 — Environmental Statement, Chapter 12: Noise and Vibration

12.1 Introduction

This chapter describes the noise and vibration assessment undertaken for the Proposed Scheme. It follows the National Policy Statement for National Networks and the methodology set out in the Design Manual for Roads and Bridges LA 111.

12.2 Baseline monitoring

Baseline monitoring ran for two weeks in September. Survey points were selected in accordance with BS 4142 and agreed with the local authority environmental health officer prior to deployment.

12.4 Assessment of effects

The predicted daytime level at receptor R7 is 54 dB LAeq,16h. Against a baseline of 47 dB this is a significant adverse effect in the terms of the assessment methodology, and mitigation is therefore required.

Receptor	Baseline	Predicted
R7	47	54
R8	52	53

12.7 Residual effects and monitoring

Mitigation is proposed at chainage 4+200 in the form of a three metre acoustic barrier. With that mitigation in place the residual effect at receptor R7 is not significant.

Monitoring during construction will be secured by a requirement in the draft Development Consent Order.